MMPCA Model Development

Prechecks before creating model

1. UOM for all the attributes must be in Type Level (SI Unit) in “Asset Type Attributes” sheet
2. UOM for all the attributes must be in Instance level in the mapping sheets (“Asset Attribute Mapping”, “Attribute Property Mapping”)

MMPCA Model Building Procedure

1. Select / Create Project with appropriate asset or asset group based on the attributes required in the model



2. Create new model with Model Category as “Anomaly” and Model template as “MMPCA”





3. To add new attributes use source as “Asset Model” and include the child asset





4. Search for required attributes, drag and drop on the dashboard



5. Go to “NEXT” section, Update the Window size and Interval



6. Select the interval for training/baseline



7. Manually clean the data using the “Clean Data” button for baseline intervals

8. Add baseline period



9. Go to Next Section and train data





10. Once training is completed, check the score of training (score above 90 can be considered good)



11. After training, model can be published by clicking on "Finish" (Must be scheduled, preferred 10 min interval)





12. Once the model is published, download the "Training Data Summary Report"



13. Mean, Baseline SD must be updated through BCT/Sentinel for the attributes as per the "Training Data Summary Report"
14. Map the expected values through BCT from "Attribute Property Mapping" sheet
15. Enable the faults based on attribute availability, if required faults can be added as per blueprint
16. Add causes, recommendations for the faults that have been enabled

POINTS TO REMEMBER

1. Manual cleaning interval must not be more than one month period. Manual cleaning can be done multiple times over multiple intervals, but care must be taken that the interval selected is not more than one month
2. Window Size and Interval must be given even before manual cleaning and training of data
3. Expected Value tag format to add in BCT: <Asset Group>.<Asset Model>.<Attribute>.ExpectedValue